

<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									

E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com)  
 Contact: (305)-813-0053



SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS
<b>PHASE-1</b>											
<b>MASONRY</b>											
<b>UNIT MASONRY</b>											
<b>FIRST FLOOR</b>											
<b>WALL TYPE - C8 A1/S401</b>											
<b>8" CMU WALL</b>											
1	A102-A103	A1/S401		8" Solid Grouted CMU Wall W/ - #7 @ 8" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	448	10%	493	SF	\$ -	\$ -	
<b>BOND BEAM</b>											
2	A102-A103			8" Bond Beam W/ - (2)#5 Bars	55	10%	61	LF	\$ -	\$ -	
<b>STEEL ANGLE</b>											
3	A102-A103		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	9	LF	\$ -	\$ -	
<b>COMPRESSIBLE FILLER</b>											
4	A102-A103			Compressible Filler	28	10%	30	LF	\$ -	\$ -	
<b>SCAFFOLDING</b>											
5	A102-A103			Scaffolding	448	10%	493	SF	\$ -	\$ -	
<b>WALL TYPE - C8 B1/S401</b>											
<b>8" CMU WALL</b>											
6	A102-A103	B1/S401		8" Solid Grouted CMU Wall W/ - #5 @ 16" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	441	10%	485	SF	\$ -	\$ -	
<b>BOND BEAM</b>											
7	A102-A103			8" Bond Beam W/ - (2)#5 Bars	55	10%	60	LF	\$ -	\$ -	
<b>STEEL ANGLE</b>											
8	A102-A103		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	9	LF	\$ -	\$ -	
<b>COMPRESSIBLE FILLER</b>											
9	A102-A103			Compressible Filler	27	10%	30	LF	\$ -	\$ -	
<b>SCAFFOLDING</b>											
10	A102-A103			Scaffolding	441	10%	485	SF	\$ -	\$ -	
<b>WALL TYPE - C8 C1/S401</b>											
<b>8" CMU WALL</b>											

<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									

E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com) 

Contact: (305)-813-0053

SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS
11	A102-A103	C1/S401		8" Solid Grouted CMU Wall W/ - #5 @ 16" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcemnt @ 16" O.C.	441	10%	485	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
12	A102-A103			8" Bond Beam W/ - (2)#5 Bars	55	10%	60	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
13	A102-A103		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	9	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
14	A102-A103			Compressible Filler	27	10%	30	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
15	A102-A103			Scaffolding	441	10%	485	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 D1/S401</b>							
				<b>8" CMU WALL</b>							
16	A102-A103	D1/S401		8" Solid Grouted CMU Wall W/ - #7 @ 8" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcemnt @ 16" O.C.	359	10%	395	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
17	A102-A103			8" Bond Beam W/ - (2)#5 Bars	44	10%	49	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
18	A102-A103		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	7	10%	7	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
19	A102-A103			Compressible Filler	22	10%	24	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
20	A102-A103			Scaffolding	359	10%	395	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 E1/S401</b>							
				<b>8" CMU WALL</b>							
21	A102-A103	E1/S401		8" Solid Grouted CMU Wall W/ - #7 @ 8" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcemnt @ 16" O.C.	378	10%	416	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
22	A102-A103			8" Bond Beam W/ - (2)#5 Bars	47	10%	51	LF	\$ -	\$ -	

<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									

E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com)

Contact: (305)-813-0053



SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS
				<b>STEEL ANGLE</b>							
23	A102-A103		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	7	10%	8	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
24	A102-A103			Compressible Filler	23	10%	26	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
25	A102-A103			Scaffolding	378	10%	416	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 F1/S401</b>							
				<b>8" CMU WALL</b>							
26	A102-A103	F1/S401		8" Solid Grouted CMU Wall W/ - #7 @ 8" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	359	10%	395	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
27	A102-A103			8" Bond Beam W/ - (2)#5 Bars	44	10%	49	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
28	A102-A103		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	7	10%	7	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
29	A102-A103			Compressible Filler	22	10%	24	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
30	A102-A103			Scaffolding	359	10%	395	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 G1/S401</b>							
				<b>8" CMU WALL</b>							
31	A102-A103	G1/S401		8" Solid Grouted CMU Wall W/ - #7 @ 8" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	378	10%	416	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
32	A102-A103			8" Bond Beam W/ - (2)#5 Bars	47	10%	51	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
33	A102-A103		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	7	10%	8	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
34	A102-A103			Compressible Filler	23	10%	26	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							

<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									


E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com)  
Contact: (305)-813-0053



SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS
35	A102-A103			Scaffolding	378	10%	416	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 H1/S401</b>							
				<b>8" CMU WALL</b>							
36	A102-A103	H1/S401		8" Solid Grouted CMU Wall W/ - #7 @ 8" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	448	10%	493	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
37	A102-A103			8" Bond Beam W/ - (2)#5 Bars	55	10%	61	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
38	A102-A103		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	9	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
39	A102-A103			Compressible Filler	28	10%	30	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
40	A102-A103			Scaffolding	448	10%	493	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 I1/S401</b>							
				<b>8" CMU WALL</b>							
41	A102-A103	I1/S401		8" Solid Grouted CMU Wall W/ - #5 @ 16" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	441	10%	485	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
42	A102-A103			8" Bond Beam W/ - (2)#5 Bars	55	10%	60	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
43	A102-A103		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	9	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
44	A102-A103			Compressible Filler	27	10%	30	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
45	A102-A103			Scaffolding	441	10%	485	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 J1/S401</b>							
				<b>8" CMU WALL</b>							
46	A102-A103	J1/S401		8" Solid Grouted CMU Wall W/ - #5 @ 16" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	441	10%	485	SF	\$ -	\$ -	

<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									

E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com)  
 Contact: (305)-813-0053



SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS
				<b>BOND BEAM</b>							
47	A102-A103			8" Bond Beam W/ - (2)#5 Bars	55	10%	60	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
48	A102-A103		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	9	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
49	A102-A103			Compressible Filler	27	10%	30	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
50	A102-A103			Scaffolding	441	10%	485	SF	\$ -	\$ -	
				<b>SECOND FLOOR</b>							
				<b>WALL TYPE - C8 A2/S402</b>							
				<b>8" CMU WALL</b>							
51	A104-A105	A2/S402		8" Solid Grouted CMU Wall W/ - #5 @ 8" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcemnt @ 16" O.C.	360	10%	396	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
52	A104-A105			8" Bond Beam W/ - (2)#5 Bars	55	10%	61	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
53	A104-A105		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	9	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
54	A104-A105			Compressible Filler	28	10%	30	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
55	A104-A105			Scaffolding	360	10%	396	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 B2/S402</b>							
				<b>8" CMU WALL</b>							
56	A104-A105	B2/S402		8" Solid Grouted CMU Wall W/ - #5 @ 24" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcemnt @ 16" O.C.	350	10%	385	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
57	A104-A105			8" Bond Beam W/ - (2)#5 Bars	34	10%	37	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							

<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									

E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com)  
 Contact: (305)-813-0053



SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS
58	A104-A105		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	8	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
59	A104-A105			Compressible Filler	27	10%	30	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
60	A104-A105			Scaffolding	350	10%	385	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 C2/S402</b>							
				<b>8" CMU WALL</b>							
61	A104-A105	C2/S402		8" Solid Grouted CMU Wall W/ - #5 @ 24" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	350	10%	385	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
62	A104-A105			8" Bond Beam W/ - (2)#5 Bars	34	10%	37	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
63	A104-A105		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	8	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
64	A104-A105			Compressible Filler	27	10%	30	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
65	A104-A105			Scaffolding	350	10%	385	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 D2/S402</b>							
				<b>8" CMU WALL</b>							
66	A104-A105	D2/S402		8" Solid Grouted CMU Wall W/ - #6 @ 8" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	290	10%	319	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
67	A104-A105			8" Bond Beam W/ - (2)#5 Bars	45	10%	49	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
68	A104-A105		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	7	10%	7	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
69	A104-A105			Compressible Filler	22	10%	25	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
70	A104-A105			Scaffolding	290	10%	319	SF	\$ -	\$ -	


<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									

E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com)  
Contact: (305)-813-0053



SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS
				<b>WALL TYPE - C8 E2/S402</b>							
				<b>8" CMU WALL</b>							
71	A104-A105	E2/S402		8" Solid Grouted CMU Wall W/ - #5 @ 8" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	272	10%	299	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
72	A104-A105			8" Bond Beam W/ - (2)#5 Bars	42	10%	46	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
73	A104-A105		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	6	10%	7	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
74	A104-A105			Compressible Filler	29	10%	32	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
75	A104-A105			Scaffolding	272	10%	299	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 F2/S402</b>							
				<b>8" CMU WALL</b>							
76	A104-A105	F2/S402		8" Solid Grouted CMU Wall W/ - #5 @ 8" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	290	10%	319	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
77	A104-A105			8" Bond Beam W/ - (2)#5 Bars	45	10%	49	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
78	A104-A105		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	7	10%	7	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
79	A104-A105			Compressible Filler	22	10%	25	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
80	A104-A105			Scaffolding	290	10%	319	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 G2/S402</b>							
				<b>8" CMU WALL</b>							
81	A102-A103	G2/S402		8" Solid Grouted CMU Wall W/ - #5 @ 8" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	304	10%	335	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							

<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									

E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com) 

Contact: (305)-813-0053

SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS
82	A102-A103			8" Bond Beam W/ - (2)#5 Bars <b>STEEL ANGLE</b>	47	10%	51	LF	\$ -	\$ -	
83	A102-A103		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side <b>COMPRESSIBLE FILLER</b>	7	10%	8	LF	\$ -	\$ -	
84	A102-A103			Compressible Filler <b>SCAFFOLDING</b>	23	10%	26	LF	\$ -	\$ -	
85	A102-A103			Scaffolding <b>WALL TYPE - C8 H2/S402</b>	304	10%	334	SF	\$ -	\$ -	
86	A104-A105	H2/S402		8" Solid Grouted CMU Wall W/ - #5 @ 8" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C. <b>8" CMU WALL</b>	360	10%	396	SF	\$ -	\$ -	
87	A104-A105			8" Bond Beam W/ - (2)#5 Bars <b>BOND BEAM</b>	55	10%	61	LF	\$ -	\$ -	
88	A104-A105		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side <b>STEEL ANGLE</b>	8	10%	9	LF	\$ -	\$ -	
89	A104-A105			Compressible Filler <b>COMPRESSIBLE FILLER</b>	28	10%	30	LF	\$ -	\$ -	
90	A104-A105			Scaffolding <b>SCAFFOLDING</b>	360	10%	396	SF	\$ -	\$ -	
91	A104-A105	I2/S402		8" Solid Grouted CMU Wall W/ - #5 @ 24" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C. <b>8" CMU WALL</b>	355	10%	390	SF	\$ -	\$ -	
92	A104-A105			8" Bond Beam W/ - (2)#5 Bars <b>BOND BEAM</b>	55	10%	60	LF	\$ -	\$ -	
93	A104-A105		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side <b>STEEL ANGLE</b>	8	10%	9	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							

<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									

E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com)  
 Contact: (305)-813-0053



SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS
94	A104-A105			Compressible Filler	27	10%	30	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
95	A104-A105			Scaffolding	355	10%	391	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 J2/S402</b>							
				<b>8" CMU WALL</b>							
96	A104-A105	J2/S402		8" Solid Grouted CMU Wall W/ - #5 @ 24" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	355	10%	390	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
97	A104-A105			8" Bond Beam W/ - (2)#5 Bars	55	10%	60	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
98	A104-A105		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	9	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
99	A104-A105			Compressible Filler	27	10%	30	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
100	A104-A105			Scaffolding	355	10%	391	SF	\$ -	\$ -	
				<b>THIRD FLOOR</b>							
				<b>WALL TYPE - C8 A3/S403</b>							
				<b>8" CMU WALL</b>							
101	A106-A107	A3/S403		8" Solid Grouted CMU Wall W/ - #5 @ 24" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	351	10%	386	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
102	A106-A107			8" Bond Beam W/ - (2)#5 Bars	55	10%	61	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
103	A106-A107		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	9	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
104	A106-A107			Compressible Filler	28	10%	30	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
105	A106-A107			Scaffolding	351	10%	386	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 B3/S403</b>							

<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									

E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com)  
Contact: (305)-813-0053




SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS
				<b>8" CMU WALL</b>							
106	A106-A107	B3/S403		8" Solid Grouted CMU Wall W/ - #4 @ 24" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcemnt @ 16" O.C.	341	10%	375	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
107	A106-A107			8" Bond Beam W/ - (2)#5 Bars	54	10%	59	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
108	A106-A107		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	8	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
109	A106-A107			Compressible Filler	27	10%	30	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
110	A106-A107			Scaffolding	341	10%	375	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 C3/S403</b>							
				<b>8" CMU WALL</b>							
111	A106-A107	C3/S403		8" Solid Grouted CMU Wall W/ - #4 @ 24" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcemnt @ 16" O.C.	341	10%	375	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
112	A106-A107			8" Bond Beam W/ - (2)#5 Bars	54	10%	59	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
113	A106-A107		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	8	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
114	A106-A107			Compressible Filler	27	10%	30	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
115	A106-A107			Scaffolding	341	10%	375	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 D3/S403</b>							
				<b>8" CMU WALL</b>							
116	A106-A107	D3/S403		8" Solid Grouted CMU Wall W/ - #4 @ 8" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcemnt @ 16" O.C.	286	10%	315	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							

<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									

E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com)

Contact: (305)-813-0053



SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS
117	A106-A107			8" Bond Beam W/ - (2)#5 Bars <b>STEEL ANGLE</b>	45	10%	50	LF	\$ -	\$ -	
118	A106-A107		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side <b>COMPRESSIBLE FILLER</b>	7	10%	7	LF	\$ -	\$ -	
119	A106-A107			Compressible Filler <b>SCAFFOLDING</b>	23	10%	25	LF	\$ -	\$ -	
120	A106-A107			Scaffolding <b>WALL TYPE - C8 E3/S403</b>	286	10%	315	SF	\$ -	\$ -	
121	A106-A107	E3/S403		8" Solid Grouted CMU Wall W/ - #5 @ 16" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C. <b>8" CMU WALL</b>	247	10%	272	SF	\$ -	\$ -	
122	A106-A107			8" Bond Beam W/ - (2)#5 Bars <b>BOND BEAM</b>	39	10%	43	LF	\$ -	\$ -	
123	A106-A107		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side <b>STEEL ANGLE</b>	6	10%	6	LF	\$ -	\$ -	
124	A106-A107			Compressible Filler <b>COMPRESSIBLE FILLER</b>	20	10%	21	LF	\$ -	\$ -	
125	A106-A107			Scaffolding <b>SCAFFOLDING</b>	247	10%	272	SF	\$ -	\$ -	
126	A106-A107	F3/S403		8" Solid Grouted CMU Wall W/ - #5 @ 16" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C. <b>8" CMU WALL</b>	283	10%	311	SF	\$ -	\$ -	
127	A106-A107			8" Bond Beam W/ - (2)#5 Bars <b>BOND BEAM</b>	45	10%	49	LF	\$ -	\$ -	
128	A106-A107		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side <b>STEEL ANGLE</b>	7	10%	7	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							

<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									

E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com)

Contact: (305)-813-0053



SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS
129	A106-A107			Compressible Filler	22	10%	25	LF	\$ -	\$ -	
				<u>SCAFFOLDING</u>							
130	A106-A107			Scaffolding	283	10%	311	SF	\$ -	\$ -	
				<u>WALL TYPE - C8 G3/S403</u>							
				<u>8" CMU WALL</u>							
131	A106-A107	G3/S403		8" Solid Grouted CMU Wall W/ - #4 @ 16" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	247	10%	272	SF	\$ -	\$ -	
				<u>BOND BEAM</u>							
132	A106-A107			8" Bond Beam W/ - (2)#5 Bars	39	10%	43	LF	\$ -	\$ -	
				<u>STEEL ANGLE</u>							
133	A106-A107		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	6	10%	6	LF	\$ -	\$ -	
				<u>COMPRESSIBLE FILLER</u>							
134	A106-A107			Compressible Filler	20	10%	21	LF	\$ -	\$ -	
				<u>SCAFFOLDING</u>							
135	A106-A107			Scaffolding	247	10%	272	SF	\$ -	\$ -	
				<u>WALL TYPE - C8 H3/S403</u>							
				<u>8" CMU WALL</u>							
136	A106-A107	H3/S403		8" Solid Grouted CMU Wall W/ - #4 @ 24" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	351	10%	386	SF	\$ -	\$ -	
				<u>BOND BEAM</u>							
137	A106-A107			8" Bond Beam W/ - (2)#5 Bars	55	10%	61	LF	\$ -	\$ -	
				<u>STEEL ANGLE</u>							
138	A106-A107		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	9	LF	\$ -	\$ -	
				<u>COMPRESSIBLE FILLER</u>							
139	A106-A107			Compressible Filler	28	10%	30	LF	\$ -	\$ -	
				<u>SCAFFOLDING</u>							
140	A106-A107			Scaffolding	351	10%	386	SF	\$ -	\$ -	
				<u>WALL TYPE - C8 I3/S403</u>							
				<u>8" CMU WALL</u>							

<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									

E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com)  
 Contact: (305)-813-0053



SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS
141	A106-A107	I3/S403		8" Solid Grouted CMU Wall W/ - #4 @ 24" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcemnt @ 16" O.C.	347	10%	382	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
142	A106-A107			8" Bond Beam W/ - (2)#5 Bars	55	10%	60	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
143	A106-A107		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	9	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
144	A106-A107			Compressible Filler	27	10%	30	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
145	A106-A107			Scaffolding	347	10%	382	SF	\$ -	\$ -	
				<b>WALL TYPE - C8 J3/S403</b>							
				<b>8" CMU WALL</b>							
146	A106-A107	J3/S403		8" Solid Grouted CMU Wall W/ - #4 @ 24" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcemnt @ 16" O.C.	347	10%	382	SF	\$ -	\$ -	
				<b>BOND BEAM</b>							
147	A106-A107			8" Bond Beam W/ - (2)#5 Bars	55	10%	60	LF	\$ -	\$ -	
				<b>STEEL ANGLE</b>							
148	A106-A107		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	8	10%	9	LF	\$ -	\$ -	
				<b>COMPRESSIBLE FILLER</b>							
149	A106-A107			Compressible Filler	27	10%	30	LF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
150	A106-A107			Scaffolding	347	10%	382	SF	\$ -	\$ -	
				<b>Unit Masonry Sub Total</b>							\$ -

<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									

E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com)  
 Contact: (305)-813-0053



SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS
				<b>BRICK VENEER</b>							
				<b>THIN BRICK VENEER</b>							
151	A200-A201	EXT-01/G004		<b>Brick Veneer As;</b> <b>Description:</b> 1/2" Thick Thin Brick Adhered to Tabs II Galvanized Steel Panel O/ - 6MM Rainscreen <b>Brick Color:</b> Metrobrick 710 Charcoal	17335	10%	19,068	SF	\$ -	\$ -	
152	A200-A201	EXT-02/G004		<b>Brick Veneer As;</b> <b>Description:</b> 1/2" Thick Thin Brick Adhered to Tabs II Galvanized Steel Panel O/ - 6MM Rainscreen <b>Brick Color:</b> Metrobrick 100 Alabaster Smooth	7057	10%	7,763	SF	\$ -	\$ -	
153	A200-A201	EXT-05/G004		<b>Brick Veneer As;</b> <b>Description:</b> 1/2" Thick Thin Brick Adhered to Tabs II Galvanized Steel Panel O/ - 6MM Rainscreen <b>Brick Color:</b> Metrobrick 710 Charcoal On CMU	111	10%	122	SF	\$ -	\$ -	
				<b>LOOSE LINTELS</b>							
154	A200-A201		<i>Install Only</i>	Loose Steel Angle Lintels	836	10%	919	LF	\$ -	\$ -	
				<b>INSULATION &amp; BARRIER</b>							
155	A200-A201			2" XPS, R-10 Install with Drainage Plane Behind Panel	24503	10%	26,953	SF	\$ -	\$ -	
156	A200-A201			Class 1, Vapor Impermeable WRB	24503	10%	26,953	SF	\$ -	\$ -	
				<b>SCAFFOLDING</b>							
157	A200-A201			Scaffolding	29863	10%	32,849	SF	\$ -	\$ -	
				<b>Brick Veneer Sub Total</b>							\$ -

<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									

E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com)  
 Contact: (305)-813-0053



SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS
------	-----------	------------	---------	-------------	------	-------	---------------	------	-----------------	------------	------------

<b>SUB - TOTAL</b>										\$	-	\$	-
--------------------	--	--	--	--	--	--	--	--	--	----	---	----	---

<b>OVERHEAD &amp; PROFIT</b>										20%	\$	-	\$	-
------------------------------	--	--	--	--	--	--	--	--	--	-----	----	---	----	---

<b>TOTAL BASE BID - PHASE 1</b>										\$	-	\$	-
---------------------------------	--	--	--	--	--	--	--	--	--	----	---	----	---

<b>PHASE-2</b>												
<b>MASONRY</b>												
<b>UNIT MASONRY</b>												
<b>FIRST FLOOR</b>												
<b>WALL TYPE - C8 K1&amp;L1/S401 &amp; K2&amp;L2/S402</b>												
<b>8" CMU WALL</b>												
158	A102-A103	K1&L1/S401 & K2&L2/S402		8" Solid Grouted CMU Wall W/ - #5 @ 24" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	2203	10%	2,424	SF	\$ -	\$ -		
<b>BOND BEAM</b>												
159	A102-A103			8" Bond Beam W/ - (2)#5 Bars	199	10%	219	LF	\$ -	\$ -		
<b>STEEL ANGLE</b>												
160	A102-A103		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C. Each Side	26	10%	28	LF	\$ -	\$ -		
<b>COMPRESSIBLE FILLER</b>												
161	A102-A103			Compressible Filler	99	10%	109	LF	\$ -	\$ -		
<b>SCAFFOLDING</b>												
162	A102-A103			Scaffolding	2203	10%	2,423	SF	\$ -	\$ -		
<b>WALL TYPE - C8 M1/S401 &amp; M2/S402</b>												
<b>8" CMU WALL</b>												
163	A102-A103	M1/S401 & M2/S402		8" Solid Grouted CMU Wall W/ - #5 @ 24" Vertical Reinforcement - 8GA. Dur-O-Wall Horizontal Reinforcement @ 16" O.C.	3407	10%	3,748	SF	\$ -	\$ -		
<b>BOND BEAM</b>												
164	A102-A103			8" Bond Beam W/ - (2)#5 Bars	307	10%	338	LF	\$ -	\$ -		
<b>STEEL ANGLE</b>												
165	A102-A103		<i>Install Only</i>	L-3"x3"x1/4", 6" Long @ 4'-0" O.C.	20	10%	22	SF	\$ -	\$ -		
<b>COMPRESSIBLE FILLER</b>												

<b>PROJECT</b>	-										
<b>ADDRESS</b>	-										
Date of submission	1/22/2023										
Date of plans	10/19/2022										
<b>PHASE-1</b>	\$	-									
<b>PHASE-2</b>	\$	-									

E-mail: [estimate@msbestimating.com](mailto:estimate@msbestimating.com)  
 Contact: (305)-813-0053



SR #	Sheet No.	Detail No.	CSI No.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	TOTAL UNIT COST	TOTAL COST	SUB TOTALS	
166	A102-A103			Compressible Filler	154	10%	169	LF	\$ -	\$ -		
				<b>SCAFFOLDING</b>								
167	A102-A103			Scaffolding	3407	10%	3,748	LF	\$ -	\$ -		
				<b>Unit Masonry Sub Total</b>							\$ -	
				<b>BRICK VENEER</b>								
				<b>THIN BRICK VENEER</b>								
168	A200-A201	EXT-01/G004		<b>Brick Veneer As; Description:</b> 1/2" Thick Thin Brick Adhered to Tabs II Galvanized Steel Panel O/ - 6MM Rainscreen <b>Brick Color:</b> Metrobrick 710 Charcoal	1749	10%	1,924	SF	\$ -	\$ -		
169	A200-A201	EXT-02/G004		<b>Brick Veneer As; Description:</b> 1/2" Thick Thin Brick Adhered to Tabs II Galvanized Steel Panel O/ - 6MM Rainscreen <b>Brick Color:</b> Metrobrick 100 Alabaster Smooth	1545	10%	1,699	SF	\$ -	\$ -		
170	A200-A201	EXT-05/G004		<b>Brick Veneer As; Description:</b> 1/2" Thick Thin Brick Adhered to Tabs II Galvanized Steel Panel O/ - 6MM Rainscreen <b>Brick Color:</b> Metrobrick 710 Charcoal On CMU	771	10%	849	SF	\$ -	\$ -		
				<b>LOOSE LINTELS</b>								
171	A200-A201		<i>Install Only</i>	Loose Steel Angle Lintels	81	10%	89	LF	\$ -	\$ -		
				<b>INSULATION &amp; BARRIER</b>								
172	A200-A201			2" XPS, R-10 Install with Drainage Plane Behind Panel	4065	10%	4,472	SF	\$ -	\$ -		
173	A200-A201			Class 1, Vapor Impermeable WRB	4065	10%	4,472	SF	\$ -	\$ -		
				<b>SCAFFOLDING</b>								
174	A200-A201			Scaffolding	4467	10%	4,914	SF	\$ -	\$ -		
				<b>Brick Veneer Sub Total</b>							\$ -	
<b>SUB - TOTAL</b>										\$ -	\$ -	
<b>OVERHEAD &amp; PROFIT</b>										20%	\$ -	\$ -
<b>TOTAL BASE BID - PHASE 2</b>										\$ -	\$ -	
<b>Exclusions</b>												
<b>Anything Not Mentioned Above</b>												